BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

No.BBMP/EE/DD/Ten/03/2014-15, Date:31.10.2014. **ITEM NO: 06**

SCHEDULE-B

NAME OF WORK: Annual Maintaianance of U.G.D at Abbigere main road, in Ward no. 12, in Shettyhalli Sub-Division

Sl. No	Description of work	Unit	Qty	Rates Quoted by Contractor **M/s Mahendra Enineering Works (G VENKATESH)**	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5 m and above in width, in hard soil not exceeding 1.5m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead up to 50 m. after breaking of clods Complete as per specification and direction of Engineer-in-charge of the work.	Cum	880.57	307.0	Rupees Three Hundred Seven Only
2	Providing and laying in position to required level or slope 300mm internal diameter salt glazed stoneware pipes grade A and jointing with stiff mixture of cement mortar in proportion of 1:1, testing of pipes and joints, including cost of materials, labour charges Complete as per specification and direction of Engineer-in-charge of the work.	m	602	675.0	Rupees Six Hundred Seventy Five Only
3	Constructing brick masonry circular type manhole 0.91m internal dia at bottom 0.91 m deep and 0.56m dia at top with table moulded non-modular bricks of 50 class designation 50 in cement mortar 1:4, inside cement plastered 12mm thick with cement mortar 1:3,finished with a floating coat of neat cement, foundation concrete M 10 using 40mm and downsize granite metal and making necessary channel in cement concrete M 50 with 20mm and downsixe granite metal finished with a floating coat of neat cement, with S.F.R.C. cover and frame (heavy duty, HD-20 grade designation) 560mm internal diameter confirming IS : 12592, total weight cover and frame to be not less than 182 Kg, fixed in cement concrete 1:2:4, 20mm and downsize broken granite metal, providing and removing centering, shuttering including cost of materials, labour charges, HOM of machinery, completete as per specifications.(Excavation, footrests and 12mm thick cement plaster on the external surface shall be paid separately) Complete as per specification and direction of Engineer-in-charge of the work.	Cum	40	13300.0	Rupees Thirteen Thousand Three Hundred Only

Executive Engineer

Signature of the Contractor

For Mahendra Works

Proprietor

4	Provi'' ıg and constructing burnt brick masonry with approved quality of non-modular bricks of standard size of class designation 50 (table moulded) with cement mortar 1:6 for basement and superstructure including cost of materials, labour charges, scaffolding, curing Complete as per specification and direction of Engineer-in-charge of the work.	Cum	23.44	6450.0	Rupees Six Thousand Four Hundred Fifty Only
5	Providing 20mm thick cement plaster in single coat with cement mortar 1:4, to stone masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing Complete as per specification and direction of Engineer-in-charge of the work.	Sqm	156	250.0	Rupees Two Hundred Fifty Only
6	Providing & Fixing SFRC Cover and frame 560mm (ID) Heavy Duty.. Material code No-0331., Complete as per specification and direction of Engineer-in-charge of the work.	Each	80	1000.0	Rupees One Thousand Only
7	Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m. and lift upto 1.5m including cost of all labour Complete as per specification and direction of Engineer-in-charge of the work.	Cum	328.69	80.0	Rupees Eighty Only
8	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 10 Km a)Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b)Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c)Add loading and unloading Complete as per specification and direction of Engineer-in-charge of the work.	Cum	871	80.0	Rupees Eighty Only

Signature of the Contractor

for M/s. Works

Proprietor

Executive Engineer,
Dasarahalli Division,